# BRUHAT BANGALORE MAHANAGARA PALIKE

## BILL OF QUANTITIES (BOQ)

**Name of the Work: Improvements to Roads, Drains and other works at Mariyamma Block in Ward No. 11, Kuvempunagara.**

| Sl. No. | Approved Qty. | Description | Unit | Issued to Technical Manager , KRIDL | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | **81.78** | Excavation for road, drains and similar works KSRRB 300-1. Earthwork **excavation by manual means in ordinary** soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work | Cum | 199.36 | Rupees One Hundred Ninety Nine and Thirty Six Paise Only |
| 2 | **583.20** | Removing and refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work | Sqm | 80.56 | Rupees Eighty and Fifty Six Paise Only |
| 3 | **408.24** | Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work | Sqm | 665.68 | Rupees Six Hundred Sixty Five and Sixty Eight Paise Only |
| 4 | **58.32** | Providing and **Filling in foundation with granite / trap broken** metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. etc complete as per specifications and directions of engineer in charge of the work | Cum | 2240.84 | Rupees Two Thousand Two Hundred Forty and Eighty Four Paise Only |
| 5 | **23.46** | Construction of granular sub-base by providing close graded crushed stone aggregates of granite / trap / basalt material, mixing in a mechaical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications. A. Plant Mix Method. - For Grading II Material etc complete as per specifications and directions of engineer in charge of the work | Cum | 1665.26 | Rupees One Thousand Six Hundred Sixty Five and Twenty Six Paise Only |
| 6 | **78.14** | Providing and laying in position **plain cement concrete of mix 1:4:8** with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, **in foundation**, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work | Cum | 5157.02 | Rupees Five Thousand One Hundred Fifty Seven and Two Paise Only |
| 7 | **518.40** | Providing and constructing load bearing wall with solid concrete blocks of size **400x200x200 mm** having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work | Sqm | 993.22 | Rupees Nine Hundred Ninety Three and Twenty Two Paise Only |
| 8 | **36.72** | Providing and laying in position **plain cement concrete of mix 1:2:4** with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, **in foundation, plinth and cills**, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work | Cum | 5767.46 | Rupees Five Thousand Seven Hundred Sixty Seven and Forty Six Paise Only |
| 9 | **388.80** | Providing **precast slab of 100 mm thick** including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge | Sqm | 1820.56 | Rupees One Thousand Eight Hundred Twenty and Fifty Six Paise Only |

Signature of the contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010



13/07
Executive Engir

13/07

| | Approved Qty. | Description | Unit | Issued to Technical Manager , KRIDL | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 10 | **32.71** | Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite metal coarse aggregates and fine aggregtes , with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. - **M20 (at 300Kg per cum coarse aggregate @** | Cum | 5508.82 | Rupees Five Thousand Five Hundred Eight and Eighty Two Paise Only |

1. The work should be executed as per the specification and standard specified by the PWD & Other specifications of the Bangalore
2. The work should be carried out as per the directions and instructions of the concerned Engineer
3. The Contractor should maintain the quality of work as per the standard specifications.

13/07

Executive Engineer (Byatarayanapura)
Bruhath Bangalore Mahanagara Palike

I am prepared to take up the above work at the rates quoted by me in the Schedule 'B'.

13/07

CONTRACTOR

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010